

Material	Description	Qty	Units
----------	-------------	-----	-------

PLAN NO:

## FOUNDATION/CONCRETE

Concrete - Footings		16	cuyd
Concrete Slab		13	cuyd
Rebar (Footings)		385	feet
Rod Chairs		54	each
Wire Mesh (Slab)		2	rolls
Vapor Barrier/32x100 Poly		1	rolls
Anchor Bolts		68	each

## FRAMING

Built-Up Beam	15'9 1/2"	1	each
Built-Up Beam	4'9 1/2"	1	each
Built-Up Beam	4'5"	2	each
Built-Up Beam	6'0"	1	each
Subtotal			

## WALL FRAMING

Sill Sealer		3	roll
2x4 Precut Studs	2"x4"x92 5/8"	218	each
2x6 Precut	2"x6"x92 5/8"	19	each
2x4 Lumber (Misc)	2"x4"x16'0"	49	each
Jack Stud*	2"x4"x14'0"	20	each
Metal Stud Straps 18"		109	each
Gable Framing Studs	2"x4"x8'0"	16	each
Gable Framing Studs	2"x4"x4'3"	5	each
Gable Framing Studs	2"x4"x1'4"	2	each
Opening Header*	2"x12"x10'0"	1	each
Opening Header*	2"x12"x12'0"	1	each
Opening Header*	2"x12"x14'0"	1	each
Opening Header*	2"x12"x16'0"	6	each
Top Plate	2"x4"	517	feet
P/T Sill Plate	2"x4"	259	feet
Opening Rough Sill*	2"x4"x14'0"	1	each
Opening Rough Sill*	2"x4"x16'0"	1	each
Gable Framing Plates	2"x4"	184	feet
Wall Sheathing	0 1/2"x4'0"x8'0"	45	shts
Tyvek House Wrap		1	roll
Subtotal			

## ROOF FRAMING

Common Rafter	2"x6"x20'0"	52	each
Common Rafter*	2"x6"x8'0"	3	each
Common Rafter*	2"x6"x10'0"	2	each
Common Rafter*	2"x6"x12'0"	2	each
Common Rafter*	2"x6"x14'0"	1	each
Common Rafter*	2"x6"x16'0"	4	each
Sub Fascia	2"x6"	192	feet
Valley Rafter	2"x8"	29	feet
Ridge Board	2"x8"	52	feet
Joist (Ceiling)*	2"x6"x12'0"	19	each
Joist (Ceiling)*	2"x6"x14'0"	17	each
Joist (Ceiling)*	2"x6"x16'0"	7	each
Joist (Ceiling)	2"x8"x18'0"	16	each
Roof Sheathing	0 15/32"x4'0"x8'0"	50	shts
Plywood H-Clip		199	each
Rafter Ties		80	each
Subtotal			